



## Meter Room Panel

### Bulletin 2321: Meter Room Panel Customer Responsibilities

---

Most start-up & commissioning difficulties and/or delays are the result of incorrect installation methods. Every precaution must be taken to assure the unit is installed properly and within local guidelines according to the local Authority Having Jurisdiction. Below is an overview of the expectations of the end user to prepare and install the Timpson Training Unit to ensure a successful Start-Up & Commissioning of your unit. Please review Bulletin 2320 – Meter Panel Installation Manual before beginning any installation activities.



- ✓ Site Prep: Determining the location for the Meter Room Panel is important. The location needs to be readily accessible to the operator.
- ✓ Mounting Pad: Training Meter Room Panel will need a secure and stable concrete foundation to be mounted to.
- ✓ Rigging and Mounting: All units have six mounting holes to be anchored to the concrete pad.
- ✓ Electrical Installation including
  - AC Power Supply of 120/208; 3-phase
  - Supply Conductor Sizing and General Grounding
  - Wiring from Panel to Meter Cans